
PRIMESOURCE BUILDING PRODUCTS, INC.


# SPEC DATA *Submittal Sheet # 042*

## EYELAGS - DRILL POINT

Interior suspended ceiling systems into Steel


Longer length for drywall (or insulation) into Steel.





ELDZ2

## Product Specifications



ELDZ3

| Part # | Dia. | Length | TPI | Bulk Qty | Hole Dia. | Thread Length | Flange Dia. | Point | Finish |
|---|---|---|---|---|---|---|---|---|---|
| ELDZ2 | 1/4" | 2" | 14 | 1M | 3/16" | 3/4" | 1/2" | SD/S12 | Zinc |
| ELDZ3 | 1/4" | 3" | 14 | 1M | 3/16" | 2" | 1/2" | SD/S12 | Zinc |

**Eyelag Drill Point Screws Ultimate Connection Value Chart**

| Part | Nominal Screw Dia. (in) | Shear Strength (Lbs) | Metal Gauge | Tension (Pull) Lbs 1 pc |
|---|---|---|---|---|
| ELDZ2 | 1/4" | 2491 | 22 | 500 |
| | | | 20 | 847 |
| | | | 16 | 1043 |
| | | | 12 | 2273 |
| ELDZ3 | 1/4" | 3020 | 22 | 518 |
| | | | 20 | 891 |
| | | | 16 | 1035 |
| | | | 12 | 2101 |

Ultimate Value Chart

Screws driven into steel were driven with three exposed threads on the off side of the connection, then pulled out with testing machine.

Note that all results were obtained in strict adherence to ASTM test protocol. These ultimate figures are offered only as a guide and are not guaranteed in any way by PrimeSource Building Products. A 4:1 safety ratio is recommended.

**ALL PRIMESOURCE FASTENERS ARE MANUFACTURED IN AN ISO 9002 AND ISO 14001 CERTIFIED AND APPROVED FACTORY TO PRIMESOURCE PERFORMANCE SPECIFICATIONS AND PRINT DRAWINGS.**



©2016 PrimeSource Building Products, Inc.